

15-065-00101-00-00

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 5 1974  
02-05-1974  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name D. G. Hansen Trust,

Complete Address Box #187, Logan, Kansas.

Lease Name Muilenburg Well No. 1

Location SE-NE-SE Sec. 1 Twp. 10 Rge. (E) (W) 21

County Graham Total Depth 3875'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Southwest Casing Pulling Company, Inc.,

Address Box #364, Great Bend, Kansas. License No. 399

Operation Completed: Hour 10:30 AM Day 28 Month 1 Year 1974

The above well was plugged as follows:

194'--8 5/8" Surface casing, cement circulated with 125 Sx.

3840'--5 1/2" Production casing cemented on bottom with 100 Sx. Open hole completion no plug back nor perforations indicated.

Sanded well back to 3825' and set 5 Sx. cement with dump bailer. Pulled 5 1/2" casing (835') and squeezed well initially with 5 sacks hulls and 14 sacks gel and followed with 110 Cu. Ft. cement from 875' to 550' then 8 sacks gel from 550' to 230' and followed with 30 Cu. Ft. cement from 230' to 160' then 3 sacks gel from 160' to 40' and finally 10 Cu. Ft. cement from 40' to bottom of cellar. Maximum pump-in pressure-300#. FSIP-100#.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: A. L. Dickie  
Well Plugging Supervisor

DATE 2/5/74

INV. NO. 8509-W