

KANSAS

Handwritten mark

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

MAY 26 1969

CONSERVATION DIVISION
Wichita, Kansas

05-26-1969

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-065-20223-00-00

Operator's Full Name Dane G. Hansen Trust,

Complete Address Box #187, Logan, Kansas.

Lease Name Wheeler Well No. 4

Location CN/2-S/2-SW Sec. 8 Twp. 10 Rge. (E) (W) 21

County Graham Total Depth 3838'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor C & G Drilling, Incorporated.

Address 1107 Union National Bank Building, Wichita, Ks License No.

Operation Completed: Hour 5:15 AM Day 18 Month 5 Year 1969

The above well was plugged as follows:

186'--8 5/8" Surface casing, cement circulated with 150 Sx.
Top of Dakota section @ 700'.

Circulated hole with heavy mud. Pulled DP to 925' and displaced 100 Sx. cement thru
DP from 925' to 600'. Pulled DP to 215' and displaced 20 Sx. cement thru DP from
215' to 155'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: N. L. Dehols
Well Plugging Supervisor

DATE 5/27/69
INV. NO. 9837-4