

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

15-065-01709-00-00

Operator's Full Name D. G. Hansen Trust,

Complete Address: Logan, Kansas.

Lease Name Wheeler Well No. 3

Location CW/2 of W/2 of SW $\frac{1}{4}$  Sec. 8 Twp. 10 Rge. (E) (W) 21

County Graham Total Depth 3858

Abandoned Oil Well X Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Southwest Casing Pulling Company, Incorporated,

Address: Box # 364, Greet Bend, Kansas. License No. 399

Operation Completed: Hour 4:00PM Day 9 Month 9 Year 1967

The Above well was plugged as follows:

177'--8 5/8" Surface pipe, cement circulated with 150 Sx.  
3841'--5 1/2" Production casing cemented with 100 Sx. Dakota section from 950' to 1150'.

Sanded well back to 3825' and set 5 Sx. cement with dump bailer. Pulled 5 1/2" casing and  
squeezed well with 20 Sx. gel using 5 sacks hulls in initial gel then followed with 100  
Sx. cement from 1170' to 850', then 14 sacks gel from 850' to 200' and followed with 20  
Sx. cement from 200' to 140', then 2 sacks gel from 140' to 30' and followed with 10 Sx.  
cement from 30' to cellar. Maximum pump-in pressure 400#. Final shut-in pressure 200#.

(Recovered 2920' 5 1/2" casing)

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 9/13/67

INV. NO. 6315-W

SEP 18 1967  
09-18-1967  
CONSERVATION DIVISION  
WICHITA, KANSAS

Signed: W. L. Nichols  
Well Plugging Supervisor