 KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

15-065-19118-00-

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 7 1969  
CONSERVATION DIVISION  
Wichita, Kansas  
10-07-1969

Operator's Full Name National Cooperative Refinery Association.

Complete Address Box #6, Great Bend, Kansas.

Lease Name Wheeler Well No. 1

Location SE-NE-SW Sec. 8 Twp. 10 Rge. (E) (W) 21

County Graham Total Depth 3883'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Globe Cementing, Incorporated.

Address Plainville, Kansas. License No. \_\_\_\_\_

Operation Completed: Hour 2:00 PM Day 2 Month 10 Year 1969


The above well was plugged as follows:

245'--8 5/8" Surface casing, cement circulated.  
3882'--5 1/2" Production casing cemented on bottom with 125 Sx. Bridge plug @ 3822'. Top perforations from 364.1' to 364.6'. 5 1/2" has been squeezed thru holes @ 1191' and 1250' with 300 Sx. cement. Hole in 5 1/2" at an undetermined depth.

Attempted to pump into annulus with clear water but was unable to do so @ 500# pressure.  
Squeezed well initially with 1 sack hulls then 50 Sx. cement from 3822' to 3600' then 43 sacks gel from 3600' to 400' and followed with 25 sacks cement from 400' to bottom of cellar. Maximum pump-in pressure--1500#. Final shut-in pressure--750#.

I hereby certify that the above well was plugged as herein stated.

INVOICED  
DATE 10/7/69  
INV. NO. 605-w

Signed:   
Well Plugging Supervisor