

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

MAY 19 1965
05-19-1965
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

15-065-30050-00-00

Operator's Full Name Petroleum, Incorporated,

Complete Address: 352 North Broadway, Wichita, Kansas.

Lease Name Clary Well No. 2

Location SE-NE-NW Sec. 13 Twp. 10 Rge. (E) (W) 21

County Graham Total Depth 3903

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Garvey Drilling Company,

Address: Route 2, Great Bend, Kansas License No.

Operation Completed: Hour 8:45PM Day 16 Month 5 Year 1965

The Above well was plugged as follows:

215'--8 5/8" Surface pipe, cement circulated with 175 Sx.
Circulated hole with heavy mud, set plug @ 540 and displaced 20 Sx. cement
thru DP. Heavy mud to 210', set plug and displaced 20 Sx. cement thru DP.
Heavy mud to 40', set plug with 1/2 sack hulls and 10 Sx. cement to bottom of
cellar. After top plug was run noticed plugs were slipping, let hole set
12 hours, ran measuring line and found top of cement @ 30' below rotary table.
Filled hole to bottom of cellar with 8 additional sacks cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: K. L. Nichols
Well Plugging Supervisor

DATE 5/19/65
INV. NO. 1181-W