

KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

7/7/61  
JUL 7 1961

CONSERVATION DIVISION  
Wichita, Kansas

TO:  
J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

File No. \_\_\_\_\_ County: Rooks

Location: SE NE NW Sec. 4 Twp. 9 Rge. \_\_\_\_\_ (E) \_\_\_\_\_ (W) 19

Name of Field: \_\_\_\_\_ Total Depth: 3457

I have this date completed supervision of plugging of:

Lease Name: Rostecil Well No. 3

Operator's Full Name: Morganstern & Specter

Complete Address: Box 661 Russell, Kansas

Plugging Contractor Lynch Pipe Pulling

Address: Great Bend, Kansas License No. ~~458~~ 457

Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereafter indicated: \_\_\_\_\_

Was any delay in plugging operations caused by Conservation Division Agent?

Yes \_\_\_\_\_ No

If yes how long? \_\_\_\_\_ Reason: \_\_\_\_\_

Operation Completed: Hour 1PM Day 4 Month 7 Year 61

The above well was plugged as follows:

8 5/8" 1424' circulated with cement - 13" 191' circulated with cement -  
5 1/2" 3428' with 200 sax cement.

PB and sand to 3100', set 4 sax cement with dump bailer, pulled 2455' 5 1/2" to  
500', circulated hole with heavy mud through 5 1/2" at 500', (20 sax Gel),  
displaced 20 sax cement through 5 1/2" at 500', heavy mud to 180', displaced  
20 sax cement through 5 1/2" at 180', heavy mud to 35', set bridge and 10 sax  
cement to bottom cellar.

Mudding and cementing by Lynch Pipe Pulling Pump truck.

Signed: [Signature]  
Conservation Division Agent

Reviewed: [Signature]  
Field Supervisor

Remarks:

INVOICED

DATE 7/30/61

INV. NO. 3415-W