

B

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. _____

LOCATION NW SE NW

SEC. 4 TWP. 9 RGE. 19

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 7 Lease Rostocil

Operator Skelly Oil Co Address Box 391 Hutchinson, Kans

Field _____ County Rooks

Total Depth 3456 Feet.

Plugging Contractor Ace Pipe Pulling

Plugging Contractor's License No. 2

Address _____

(Describe briefly the manner in which the well was plugged)

13" at 183' Circulated with cement - 8 5/8" at 1453' circulated with 700 sax cement - 5 1/2" at 3450' with 200 sax cement behind.

Baker plugs to 3204' - perforated at 3193'

Filled with sand to 3185', set 4 sax cement with dump bailer,

pulled 2400' 5 1/2" - filled with mud to 300', set rock and 15 sax cement, mud to 35', set rock and 10 sax cement to bottom cellar.

RECEIVED
STATE CORPORATION COMMISSION
3/29/56
MAR 24 1956

Edwin Petty
District Conservation Agent

Date

3-23-56

PLUGGING
FILE SEC 4 T 9 R 19W
BOOK PAGE 41 LINE 13

CONSERVATION DIVISION
Wichita, Kansas