

15-163-03030-00-06

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

8/14/61
AUG 14 1961

CONSERVATION DIVISION
Wichita, Kansas

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. _____ County: _____ Rooks _____

Location: NW NW SE Sec. 4 Twp. 9 Rge. _____ (E) _____ (W) 19

Name of Field: _____ Total Depth: 3419

I have this date completed supervision of plugging of:

Lease Name: Mc Clellan Well No. B-1

Operator's Full Name: Natural Gas & Oil

Complete Address: Box 1150 Great Bend, Kansas

Plugging Contractor: Knight Casing Pulling Co

Address: Chase, Kansas License No. 436

Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes _____ No

If yes how long? _____ Reason: _____

Operation Completed: Hour 2PM Day 2 Month 8 Year 61

The above well was plugged as follows:

8 5/8" 1223' circulated with cement - 5 1/2" 3419' with 7 65 sax cement. PB 3270', perforated 3209'

Filled with sand to 3190', set 4 sax cement with dump bailer, pulled 2385' 5 1/2" to 600', mudded hole with gel mud through 5 1/2" (15 sax Gel), displaced 20 sax cement through 5 1/2" at 500', heavy mud to 180', displaced 20 sax cement through 5 1/2" at 180', heavy mud to 35', set bridge and filled to bottom cellar with cement.

Mudding and cementing by Knight Casing Pulling pump truck.

Signed: [Signature]
Conservation Division Agent

Reviewed: [Signature]
Field Supervisor

Remarks:

INVOICED
DATE 8/18/61
INV. NO. 3593-W