



DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 88-32
LOCATION NE NE SW
SEC. 4 TWP. 9 RGE. 19

Dry Hole _____ Abandoned Oil Well Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1-0 Lease Mc Clelland "C"
Operator Westgate Greenland Address Wichita, Kans
Field _____ County Rooks
Total Depth 3429 Feet.

(Describe briefly the manner in which the well was plugged)

10 3/4" at 151' circulated with cement - 5 1/2" at 3427' with
80 sax cement behind.

Chat to 3415', set 4 sax cement with dump bailer - pulled 487'
5 1/2" - filled with mud to 150', set rock and 20 sax cement -
mud to 30', set rock and 10 sax cement to bottom cellar.

PLUGGING
FILE SEC 4 T 9 R 19
BOOK PAGE 88 LINE 32

5/15/53

Edon Terry
District Conservation Agent
Date 4-29-53