

15-163-19053-00-00

TK

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

TO:
J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. _____ County: Rooks

Location: SE SE NW Sec. 4 Twp. _____ Rge. 9 (E) 19 (W) _____

Name of Field: _____ Total Depth: 3471

I have this date completed supervision of plugging of:

Lease Name: Rosticil Well No. 5

Operator's Full Name: Morganstern & Specter

Complete Address: Box 661 Russell, Kansas

Plugging Contractor Lynch Pipe Pulling

Address: Great Bend, Kans License No. 457

Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent?

Yes _____ No

If yes how long? _____ Reason: _____

Operation Completed: Hour 4:30PM Day 28 Month 6 Year 61

The above well was plugged as follows:

8 5/8" 1453' circulated with cement - 5 1/2" 3446' with 200 sax cement.

P.B. with sand to ~~311~~ 3100', set 4 sax cement with dump bailer, pulled

2600', 5 1/2" to 500', circulated hole with heavy mud through 5 1/2" - displaced

20 sax cement through 5 1/2" at 500', heavy mud to 180', displaced 20 sax cement

through 5 1/2" at 180', heavy mud to 35', set bridge and filled to bottom

cellar with cement.

Mudding and cementing by Lynch Co pump truck.

Signed: *Edward Perry*
Conservation Division Agent

Reviewed: *Harold Mollen*
Field Supervisor

Remarks:

INVOICED
DATE 7/20/61
INV. NO. 3413-W