

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

15-163-19318-00-00

Operator's Full Name Per One

Complete Address: Great Bend Kans.

Lease Name Rostocil Well No. B1

Location Sw Nw Nw Sec. 4 Twp. 9 Rge. 19 (E) (W)

County Rooks Total Depth 3478

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Glen V Smith

Address: Great Bend Kans. License No. \_\_\_\_\_

Operation Completed: Hour 10 P Day 16 Month Feb Year 1966

The Above well was plugged as follows:

T. N. - 3478 - 8 5/8" at 255' - 5 1/2" at 3468'

Sand to 3450 and 3 sac cement with dump bailer

Pulled pipe to 603' and circulated mud 12 sac

Pulled pipe to 495' and displaced 20 sac cement

with pump. Pulled pipe to 250' and displaced 20

sac cement with pump. Pulled pipe out of

hole and built bridge at 40ft and displaced 10

sac cement.

**RECEIVED**  
STATE CORPORATION COMMISSION  
2/18/66  
FEB 18 1966

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Glen P. Luke  
Well Plugging Supervisor

DATE \_\_\_\_\_  
INV. NO. \_\_\_\_\_

CONSERVATION DIVISION  
Wichita, Kansas