


DISTRICT CONSERVATION AGENT'S REPORT



TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 49-10

LOCATION NE-NE-SW

SEC. 34 TWP. 9 RGE. 21

Dry Hole X Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Muchard

Operator C. H. Drilling Co. Address 206 N. W. Bldg. Wichita Kans

Field _____ County Graham

Total Depth 3927 Feet.

(Describe briefly the manner in which the well was plugged)

Surfoc Pipe 8 3/8 - 245 ft. Circulated with cement.
3 1/2 casing at 3704 ft. Cemented with 100 sacks cement.
Plugged back to 3835 ft with sand - Mixed 4 sacks
of cement at 3835 ft - Shot off & Pulled the 3 1/2 casing -
Mud to 215 ft - Set Rock Bridge & 15 sacks of cement
at 215 ft. Mud to 40 ft. B. Bridge & 10 sacks of
cement at the Surfoc -
Patterson Pipe Pulling Co. - Plugging Contractor

STATE CORPORATION COMMISSION
1-2-51
JAN X 2 1951

CONSERVATION DIVISION
Wichita, Kansas

C. H. Stouffer
District Conservation Agent

Date 12-28-50

PLUGGING
FILE SEC 34 T 9 R 21
BOOK PAGE 49 LINE 10