

DISTRICT CONSERVATION AGENT'S REPORT

CR

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. _____

LOCATION SW NW SE

SEC. 34 TWP. 9 RGE. 21

Dry Hole _____ Abandoned Oil Well Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. _____ Lease Desair

Operator Phillips Pet Co Address _____

Field _____ County Graham

Total Depth 3877 Feet.

Plugging Contractor Halliburton Cementing Co

Plugging Contractor's License No. _____

Address _____

(Describe Briefly the manner in which the well was plugged)

8 5/8" at 346' circulated with cement - 5 1/2" at 3875' with 150

sax cement behind - perforated at 1800' and circulated with

cement from 1800' to 0' - No pipe recovery.

Pumped hole full commercial mud (35 sax Gel 0), pumped cementing

plug to 605' followed by 75 sax cement - cement 605' to 0'.

Mudding and Cementing by Halliburton Cementing Co. 900# pump pressure.

E. J. Terry
District Conservation Agent

Date 8-21-57

PLUGGING
FILE SEC 34 T 9 R 21W
BOOK PAGE 37 LINE 6

8-23-57