

R

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

DEC 14 1964
12-14-64
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Morgenstern & Specter, Incorporated,

Complete Address: Box #661, Russell, Kansas.

Lease Name Desair Well No. 1

Location CSE-SE-SE Sec. 34 Twp. 9 Rge. (E) (W) 21

County Graham Total Depth 3862

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Knight Casing Pulling Company,

Address: Box #405, Chase, Kansas. License No. 436

Operation Completed: Hour 3:00PM Day 9 Month 12 Year 1964

The Above well was plugged as follows:

1825'--8 5/8" Surface pipe, cement circulated,

3855 1/2'--5 1/2" Production casing cemented with 200 Sx.

sanded well back to 3850' and set 5 Sx. cement with dump bailer.

Pulled 5 1/2" casing. Check top of fluid and found it at 370'. Bailed hole

to 450', set rock bridge and filled hole to bottom of cellar with 5 to 1

Redi-Mix. (Used 7 yards) Recovered 2830' 5 1/2" casing.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 12-14-64
INV. NO. 330-W

Signed: H. L. Nichols
Well Plugging Supervisor