

12

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

JUL 5 1973
7-5-73
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name A. L. Abercrombie, Incorporated,

Complete Address 801 Union Center Building, Wichita, Kansas.

Lease Name Desair Well No. 3

Location SW-SW-SE Sec. 34 Twp. 9 Rge. (E) (W) 21

County Graham Total Depth 3889'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Sun Oil Well Cementing, Inc.,

Address Box #69, Hays, Kansas. License No. _____

Operation Completed: Hour 12:15 PM Day 28 Month 6 Year 1973

The above well was plugged as follows:

298'---8 5/8" Surface casing, cement circulated.
3888'---5 1/2" Production casing cemented on bottom with 125 Sx. DV Tool set in the Anhydrite with cement circulated to surface (675 Sx.). Top perforations from 3661' to 3671'.

Squeezed 5 1/2" with 1 sack hulls and followed with 20 Sx. cement, then 28 sacks gel for displacement. Pressure built to 1500#. Bled back and pumped in 10 Sx. cement. Maximum Pump-in Pressure-1500#. Final Shut-in pressure-1000#.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *M. L. Nichols*
Well Plugging Supervisor

DATE 7/6/73
INV. NO. 7595-U