

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JUL 5 1973
7-5-73
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name A. L. Abercrombie, Incorporated,

Complete Address 301 Union Center Building, Wichita, Kansas.

Lease Name Desair Well No. 4

Location CE/2-SW-SE Sec. 34 Twp. 9 Rge. (E) (W)21

County Graham Total Depth 3888'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Sun Oil Well Cementing, Inc.,

Address Box #69, Hays, Kansas. License No. _____

Operation Completed: Hour 2:30 PM Day 6 Month 282 Year 1973

The above well was plugged as follows:

325'--8 5/8" Surface casing, cement circulated.
3887'--5 1/2" Production casing cemented on bottom with 125 Sx. DV Tool set in Anhydrite with cement circulated to surface. Top perforations from 3858' to 3865'.
Squeezed well with 20 Sx. cement and followed with 28 sacks gel from 3750' to 950'
and followed with 50 Sx. cement from 950' to 550' then 5 sacks gel from 550' to 50'
and finally 10 Sx. cement from 50' to bottom of cellar. Maximum pump-in pressure--
1150#. Final shut-in pressure-1000#.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: M. L. Nichols
Well Plugging Supervisor

DATE 7/6/73
INV. NO. 7596-w