

DISTRICT CONSERVATION AGENT'S REPORT

[Handwritten signature]

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 148-26

LOCATION CE 1/2 NW SE

SEC. 34 TWP. 9 RGE. 21

Dry Hole X Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 5 Lease De Sair

Operator Phillips Pet Co Address Great Bend, Kans

Field _____ County Graham

Total Depth 3890 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 342' circulated with cement - 5 1/2" at 3872 with 150 sax cement
behind - Lane Wells Plugs to 3664' Perforations at 3584'.

Filled with chat to 3570', set 4 sax cement with dump bailer,
pulled 1900' 5 1/2", filled hole with mud to 340', set plug, rock and 15 sax
cement, mud to 35', set rock and 10 sax cement to bottom cellar.

PLUGGING
FILE SEC 34 9 R
BOOK PAGE 198 LINE 26

[Handwritten Signature]
District Conservation Agent

Date 3-24-52

3-31-52