

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. 94-34

LOCATION SW SW SW

SEC. 10 TWP. 9 RGE. 22

Dry Hole \_\_\_\_\_ Abandoned Oil Well x Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. 1 Lease Swazey Swoyze

Operator Wolfson Oil Co Address Wichita Falls, Texas

Field \_\_\_\_\_ County Graham

Total Depth 3923 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 1845' circulated with cement - 5 1/2" at 3913' with  
100 sax cement behind.

Pumped cementing plug to 3910', set 5 sax cement at 3910 with  
dump bailer, pulled 2113' 5 1/2", filled hole with mud to  
250', set rock bridge and 20 sax cement, filled with mud to  
35', set rock bridge and 10 sax cement to bottom cellar.

RECEIVED  
STATE CORPORATION COMMISSION  
8-9-51

AUG 9 X 1951

CONSERVATION DIVISION  
Wichita, Kansas

[Signature]  
District Conservation Agent 7

Date 8-4-51

PLUGGING  
FILE SEC 10 T 9 R xxw  
BOOK PAGE 94 LINE 34