


KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
7-17-70
JUL 17 1970
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Black Petroleum, Inc.
Complete Address 445 Olive W. Garvey Bldg., Wichita, Kansas
Lease Name Sturgeon Well No. 1
Location G N/2 S/2 SE Sec. 29 Twp. 9 Rge. (E) (W) 22
County Graham Total Depth 3855
Abandoned Oil Well Gas Well Input Well SWD Well D & A XX
Other well as hereafter indicated
Plugging Contractor Woodman - Iannitti
Address Wichita, Kansas License No.
Operation Completed: Hour 8:15 A Day 16 Month 7 Year 1970

The above well was plugged as follows:

RTD 3855' 8 5/8 csg set at 189' cwc Cmt. Mat. 100 sk reg poz 6% gel.
at 900'
Gunned pits, circulated heavy mud, set cementing plug and displaced 70 sk cmt thru
drill pipe. Heavy mud to 200' set cementing plug and displaced 20 sk cmt thru drill
pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to base of
cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 7/17/70
INV. NO. 2240-W

Signed: [Signature]
Well Plugging Supervisor