

14

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
5-15-69
MAY 15 1969
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name George Ablah,

Complete Address 8028 Cork, Wichita, Kansas.

Lease Name Van Loenen Well No. 2

Location NE-SW-NE Sec. 10 Twp. 9 Rge. (E) (W) 22

County Graham Total Depth 3558'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated _____

Plugging Contractor H-30 Drilling, Incorporated,

Address 200 North Main, Wichita, Kansas. License No. _____

Operation Completed: Hour 1:30 PM Day 12 Month 5 Year 1969

The above well was plugged as follows:

208'---8 5/8" Surface casing, cement circulated with 150 Sx.
Top of Dakota section @ 725'.

Circulated hole with heavy mud. Pulled DP to 950' and displaced 100 Sx. cement thru
DP from 950' to 625'. Pulled DP to 215' and displaced 20 Sx. cement thru DP from
215' to 155'. Pulled DP, set bridge @ 140' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 5/15/69
INV. NO. 9765-4

Signed: N. L. Nichols
Well Plugging Supervisor