

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
OCT 4 1971
10-4-71
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Petroleum, Incorporated,
Complete Address 300 West Douglas, Wichita, Kansas.
Lease Name Van Loenen Well No. B-1
Location App: NE-SE Sec. 10 Twp. 9 Rge. (E) (W) 22
County Graham Total Depth 3560'
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated
Plugging Contractor Garvey Drilling Company,
Address Box #1164, Great Bend, Kansas. License No.
Operation Completed: Hour 8:45 AM Day 1 Month 10 Year 1971

The above well was plugged as follows:

205'--8 5/8" Surface casing, cement circulated with 175 Sx.
Top of Dakota section @ 725'.

Circulated hole with heavy mud. Pulled DP to 950' and displaced 100 Sx. cement thru
DP from 950' to 625'. Pulled DP to 215' and displaced 20 Sx. cement thru DP from
215' to 155'. Pulled DP, set bridge @ 40' with $\frac{1}{2}$ sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 10/5/71
INV. NO. 4424-u

Signed: N. L. Dechek
Well Plugging Supervisor