



Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAY 29 1974
5-29-74
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Chief Drilling Company, Incorporated & P.S. Petroleum Company,

Complete Address 905 Century Plaza, Wichita, Kansas.

Lease Name Jeffers etal Well No. 1

Location CE/2-NW-SE Sec. 29 Twp. 9 Rge. (E) (W) 22

County Graham Total Depth 3860'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Chief Drilling Company, Incorporated,

Address Above License No.

Operation Completed: Hour 9:30 PM Day 26 Month 5 Year 1974

The above well was plugged as follows:

200'--8 5/8" Surface casing, cement circulated with 150 Sx.
Top of Dakota section @ 825'.

200'--8 5/8" Surface casing, cement circulated with 150 Sx.
Top of Dakota section @ 825'.

Circulated hole with heavy mud. Pulled DP to 1050' and displaced 110 Cu. Ft. cement
thru DP from 1050' to 775'. Pulled DP to 215' and displaced 30 Cu. Ft. cement thru
DP from 215' to 140'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *W. L. Nichols*
Well Plugging Supervisor

INVOICED

DATE 5/30/74
INV. NO. 9206-W