

DISTRICT CONSERVATION AGENT'S REPORT

15

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. 124-38

LOCATION SE-SE-SE

SEC. 15 TWP, 9 RGE. 19-W

Dry Hole X Abandoned Oil Well          Abandoned Gas Well         

I have today completed supervision of plugging of:

Well No. 1 Lease Bartos

Operator Wataite-Greene and Co. Address 1022 Union National Bank Bldg - Wichita

Field          County Beck

Total Depth 3583 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 3/8" - 160ft - cemented all around  
5 1/2" casing set at 3560ft. cemented with 125 sacks cement  
Plugged back down bottom to 3306ft & tested - 210 G.P.  
Set Plug at 3275ft & 6 sacks cement with dump  
boiler - shot off & cemented 2500ft of 5 1/2" casing.  
Filled hole with mud to 160ft - Set Plug & 15 sacks cement  
Surface Plug 25ft below the surface & 10 sacks cement.  
Filling hole to surface

Bill Morgan -  
Pipe Runner & Plugger

C. H. Stouffer  
District Conservation Agent  
Date 8-30-44

