

DISTRICT CONSERVATION AGENT'S REPORT

B

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 25-1
LOCATION SE SE NW
SEC. 15 TWP. 9 RGE. 19

Dry Hole Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 2 Lease _____ Casey
Operator Westgate Greenland Address Wichita, Kans
Field _____ County Rooks
Total Depth 3552 Feet.

(Describe briefly the manner in which the well was plugged)

10 3/4" at 200' circulated with cement - 7" at 3501' with
100 sax cement behind.

Filled with sand to 3590', set 5 sax cement with dump bailer,
pulled 850' 7" casing, mud to 200', set rock and 20 sax
cement, mud to 35', set rock and 10 sax cement to bottom
cellar.

RECEIVED
STATE CORPORATION COMMISSION
PLUGGING
FILE SEC 15 T 9 R 19 JUN 28 1952
PAGE 25 CONSERVATION DIVISION
Kansas

[Signature]
District Conservation Agent
Date 6-28-52