

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAY 4 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Landes Exploration Co.

Complete Address P/O. Box 867 Magnolia, Ark.

Lease Name Moon Well No. 1

Location NW SE SW Sec. 25 Twp. 9 Rge. (E) (W) 18

County Rooks Total Depth 3660'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor L.J. Dreiling Drlg.

Address Victoria, Kansas License No.

Operation Completed: Hour 9A Day 30 Month 4 Year 1970

The above well was plugged as follows:

RTD 3660' 8 5/8 csg set at 216' cwc 150 sk Cmt. Mat. 50-50 poz 6% gel.

Gunned pits, circulated heavy mud, set cementing plug at 660' and displaced 70 sk

cmt thru drill pipe. Heavy mud to 210' set cementing plug and displaced 20 sk cmt

thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt

to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 5/4/70

INV. NO. 1834-W

Signed: Leo J. Massey
Well Plugging Supervisor