



Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

15-163-20248-00-00

OCT 21 1974
10-24-1974
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Tilco, Inc.

Complete Address 400 Century Plaza, Wichita, Kansas 67202

Lease Name Darland Well No. 3

Location NW NE NE Sec. 11 Twp. 10 Rge. (E) (W) 17

County Rooks Total Depth 3525'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Kelso Pipe Pulling

Address Box 176 Chase, Kansas 67524 License No. 683

Operation Completed: Hour 3 P Day 18 Month 10 Year 1974

The above well was plugged as follows:

Total Depth 3525' 8 5/8 csg set at 209' cwc 150 sx.

5 1/2" csg set at 3523' cw 150 sx cem.

5 1/2" csg PBTD 3515' & perf. (3188+3192')

Set 5 1/2" wood plug at 3000' -poured 10' sd -dumped 4 sk cem W/dump bailer. (3000-2950)

Cutoff & recovered 2092' of 5 1/2" csg.

Pumped down 8 5/8 csg with 20 sk gel & water W/300 lbs hulls -70 sx 50-50 poz 6% -

8 sk gel & water -released 8 5/8 plug & pumped 50 sk 50-50 poz 6% by Allied.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 10/23/74
INV. NO. 154-W

Signed: Geo F. Massey
Well Plugging Supervisor