

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT STATE CORPORATION COMMISSION

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

RECEIVED  
OCT 21 1974  
10-21-1974  
CONSERVATION DIVISION  
Wichita, Kansas

15-163-20247-00-00

Operator's Full Name Tilco, Inc.

Complete Address 400 Century Plaza, Wichita, Kansas 67202

Lease Name Darland Well No. 2

Location NW NW NE Sec. 11 Twp. 10 Rge. (E) (W) 17

County Rooks Total Depth 3487'

Abandoned Oil Well XX Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Kelso Pipe Pulling

Address Box 176, Chase, Kansas 67524 License No. 683

Operation Completed: Hour 4:30 P Day 18 Month 10 Year 1974

The above well was plugged as follows:

Total Depth 3487' 8 5/8 csg set at 209' cwc 150 sx.

5 1/2 csg set at 3485' cw 150 sx cem.

5 1/2 csg PBD 3285' & perf. (3160-3166)

Set 5 1/2 wood plug at 3000' -poured 10' sd -dumped 4 sx cem W/dump bailer. (3000-2950)

Cutoff & recovered A/2300' of 5 1/2 csg.

Pumped down 8 5/8 csg with 20 sx gel & water W/300 lbs hulls -70 sx 50-50 poz 6% -

8 sx gel & water -released 8 5/8 plug & pumped 50 sx 50-50 poz 6% by Allied.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo Z. Massey  
Well Plugging Supervisor

DATE 10/23/74  
153-W