

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
02-14-1975
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

15-163 - 20249 - 00 - 00

Operator's Full Name Tilco, Inc.
Complete Address 400 Century Plaza, Wichita, Kansas 67202
Lease Name Rolfe "A" Well No. 1
Location NW NW NW Sec. 11 Twp. 10 Rge. (E) (W) 17
County W Rooks Total Depth 3510'
Abandoned Oil Well XX Gas Well Input Well SWD Well D & A
Other well as hereafter indicated
Plugging Contractor Kelso Pipe Pulling
Address Box 176, Chase, Kansas 67524 License No. 683
Operation Completed: Hour 11:15 A Day 12 Month 2 Year 1975

The above well was plugged as follows:

Total Depth 3510' 8 5/8 csg set at 209' cwc 150 sk.
5 1/2 csg set at 3508' cw 150 sk cmt.
Filled 5 1/2 csg W/sd (3510-3485) dumped 4 sk cmt W/dump bailer. (3485-3455)
Cutoff & recovered 2407' of 5 1/2 csg.
Mixed & pumped down 8 5/8 csg with 20 sk gel & water W/300 lbs hulls -70 sk
50-50 poz cem 6% -8 sk gel & water -released plug & 50 sk 50-50 poz 6%.by
Allied Cementing Co.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Geo. Z. Massey
Well Plugging Supervisor

DATE 2/14/75
INV. NO. 834-W