

KANSAS

FORM CP-3  
Rev. 1-8-82

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT REPORT

API Number 15-163 -21,725 -00-00

200 Colorado Derby Building  
Wichita, KS 67202

Operator's Full Name T & W Oil Co.

Complete Address 400 E. 23st. Hays, Ks. 67601

Lease Name Becher Well No. 1

Location NW SE SW Sec. 19 Twp. 10 Rge. 17 (East) (West)

County Rooks Total Depth 3730'

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D&A XXX

Other well as hereinafter indicated     

Plugging Contractor Big Three Drilling Co.

Address Box 52, Gorham, Ks. 67640 License No.     

Operation Completed: Hour: 12:30 AM Day: 7 Month: 7 Year: 19 82

Plugging Operations attended by Agent?: All      Part      None XXX

The above well was plugged as follows:

8 5/8"-281' S.P. cuc. w/200 sacks common-2% Gel.-3% Cal.Cl.

Ordered 150 sacks 50/50 posmix-4% Gel.-3% Gal.Cl. & 8 5/8" plug.

Spot w/drill stem w/heavy mud between all plugs.

1st plug @ 320' w/ 80 sacks cement

2nd plug @ 300' w/40 sacks cement

3rd plug-solid bridg of hulls & plug @ 40' w/10 sacks cement.

Circulate 10 sacks in rat hole & 10 sacks in mouse hole.

Amount of Surface Casing: 281' of 8 5/8"

I hereby certify that the above plugging instructions were stated herein stated.

Signed: [Signature]  
Conservation Division Agent

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 12 1982  
CONSERVATION DIVISION  
Wichita, Kansas

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

~~INVOICED~~

Signed:       
Conservation Division Agent  
DATE 7-13-82  
INV. NO. 644-W