

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-30042-00-00
Spot: CNWNENW Sec/Twnshp/Rge: 13-10S-21W
330' feet from S Section Line, 1650 feet from E Section Line
Lease/Unit Name: CLARY Well Number: 1
County: GRAHAM Total Vertical Depth: 3852 feet

Operator License No.: 6931
Op Name: BOWMAN OIL COMPANY
Address: 805 CODELL RD.
CODELL, KS 67663

Conductor Pipe: Size feet: 8/25.19
Surface Casing: Size 8.625 feet: 215 w/175 sxs cmt
Production: Size 5.5 feet: 3846 w/75 sxs cmt
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 03/06/2002 8:00 AM
Plug Co. License No.: 6931 Plug Co. Name: BOWMAN OIL COMPANY
Proposal Rcvd. from: DON BOWMAN Company: BOWMAN OIL COMPANY Phone: (785) 434-2286

Proposed Plugging Method: Ordered 250 sxs 60/40 pozmix - 10% gel - 500# hulls.
Perf casing at 1775' and 1025'.

Plugging Proposal Received By: DENNIS HAMEL WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 03/06/2002 12:00 PM KCC Agent: DENNIS HAMEL

Actual Plugging Report:

Squeezed 8 5/8" S.P. with 25 sxs cement with 100# hulls.
5 1/2" casing - Squeezed 25 sxs cement with 200# hulls, followed with 15 sxs gel,
followed with 200 sxs cement and 200# hulls mixed in cement.
Max. P.S.I. 800#. S.I.P. 500#.

RECEIVED
MAR 28 2002
WICHITA
Dennis Hamel
3/28/02

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed

Dennis L. Hamel

(TECHNICIAN)

INVOICED

DATE 4-3-02

INV. NO. 2002061604

Form CP-2/3

MAR 28 2002

22

PETROLEUM, INC.

#1 CLARY

13-10-21W
NW NE NW

Contr. GARVEY DRLG

GRAHAM

County

E 2281 KBComm 3/11/65

Comp. 5/6/65

IP PMP 25 BOPD, NW

2279 DF est

(ARB 3846-52)

LOG Tops	Depth	Datum
ANH	1750	+531
HEEB	3489	-1208
TOR	3512	-1231
LANS	3531	-1250
ARB	3804	-1525
TD	3852	-1571

Casing
 8" 215/175 sx:
 5" 3846/75 sx:
 DST 3677-3720/1', 490' MW, BHP
 1030-1000#/30", FP 90-230#:
 DST 3816-20/1', 130' OCM, BHP
 410-380#/30", FP 20-40#:
 DST 3820-30/1', 895' FREE O, BHP
 610-610#/30", FP 170-300#:
 RTD 3851: 5" 3846: DD 3852: GSO;
 POP, NAT'L;

COOPER

•		

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

GEOL: AL STUDE: