

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-035-20424-00-00  
Spot: NWSESESE Sec/Twnshp/Rge: 18-31S-6E  
547 feet from S Section Line, 408 feet from E Section Line  
Lease Name: WEIGLE Well #: 5  
County: COWLEY Total Vertical Depth: 2985 feet

Operator License No.: 4419  
Op Name: BEAR PETROLEUM, INC.  
Address: PO BOX 438  
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		2688		
PROD	4.5	2985	1056	100 SX CMT
SURF	8.625	210		85 SX CMT

\$ 97.01

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/03/2007 4:00 PM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE Phone: (620) 938-2943

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 12/03/2007 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

SANDED BACK @ 2530', DUMP BAILED 4 SXS CEMENT ON TOP. CUT CASING @ 1064', LAYED DOWN 4-1/2" CASING. RIH W/TBG @ 360', COPELAND ACID SERVICE MIXED & PUMPED 140 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. P & A COMPLETE. PLUG DOWN 1700 PM 12-3-2007. COPELAND CEMENT TICKET #32273.

Perfs:

Top	Bot	Thru	Comments
2926	2929		
2918	2920		
2896	2898		
2858	2876		
2630	2638		
2624	2628		

INVOICED  
DATE 1-4-08  
INV. NO. 2008061014

RECEIVED  
KANSAS CORPORATION COMMISSION  
JAN 02 2008  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: -096.80792,37.34664, PBTD 2688'. PERFS 2624'-28', CIBP 2688'

Plugged through: TBG

District: 02

Signed

*Duane Krueger*

(TECHNICIAN)

*PK*