

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-20841-00-00
Spot: NWSW Sec/Twnshp/Rge: 8-31S-6E
1968 feet from S Section Line, 4488 feet from E Section Line
Lease Name: RISING Well #: 5
County: COWLEY Total Vertical Depth: 2900 feet

Operator License No.: 4419
Op Name: BEAR PETROLEUM, INC.
Address: PO BOX 438
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	2980		
SURF	8.625	200		

\$ 9425

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/03/2007 1:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE Phone: (620) 938-2943

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER WitnessType: PARTIAL
Date/Time Plugging Completed: 12/03/2007 2:30 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

SANDED BACK @ 2700', DUMP BAILED 4 SXS CEMENT ON TOP. CUT CASING @ 1014', LAYED DOWN 4-1/2" CASING, RIH W/TBG @ 360'. COPELAND ACID SERVICE MIXED & PUMPED 120 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. P & A COMPLETE. PLUG DOWN 1430 PM 12-3-2007. COPELAND CEMENT TICKET #32271.

Perfs:

INVOICED
DATE 1-4-08
INV. NO. 2008061014

RECEIVED
KANSAS CORPORATION COMMISSION
JAN 02 2008
CONSERVATION DIVISION
WICHITA, KS

Remarks: -096.80423.37.36498. PBTB 2826', PERFS 2770'-2810'

Plugged through: TBG

District: 02

Signed Duane Krueger
(TECHNICIAN)