

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-015-22101-00-00  
Spot: SWNESW Sec/Twnshp/Rge: 6-23S-4E  
1650 feet from S Section Line, 3630 feet from E Section Line  
Lease Name: ED LIGGETT Well #: 4  
County: BUTLER Total Vertical Depth: 2520 feet

Operator License No.: 32444  
Op Name: HIZEY SERVICE & SUPPLY, INC.  
Address: BOX 296  
AUGUSTA, KS 67010

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	2519		100 SX CMT
SURF	8.625	201		120 SX CMT

\$ 81.90

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/19/2007 11:00 AM  
Plug Co. License No.: 32475 Plug Co. Name: BRADEN, JAMES R. DBA BRADEN PETROLEUM & WELL PLUGGING C  
Proposal Rcvd. from: MIKE KISER Company: HIZEY SERVICE & SUPPLY Phone: (316) 775-5496

Proposed Plugging Method: CONVERSATION WITH JEFF KLOCK-SHUT TUBING @ 250 AND PULL, PERF 4.5" CASING CIRCULATE CEMENT FILLING BACK SIDE 60/40 W 4% GEL

Plugging Proposal Received By: JEFF KLOCK WitnessType: PARTIAL  
Date/Time Plugging Completed: 12/19/2007 12:05 PM KCC Agent: BILL JOHNSON

Actual Plugging Report:

PULLED 265 FEET OF TUBING, SHOT 4 1/2" CASING WITH 4 SHOTS AT 260, RAN 1" TUBING TO 260 FEET INSIDE 4 1/2" CASING, PUMP CEMENT UP BACK SIDE (11:48)  
PULLED 2 JOINTS OF 1" (60') PUMP CEMENT UP INSIDE THE 4 1/2" CASING.

Perfs:

Top	Bot	Thru	Comments
2455	2460		

INVOICED

DATE 1-4-08  
INV. NO. 2008061016

RECEIVED  
KANSAS CORPORATION COMMISSION  
**JAN 02 2008**  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: CONSOLIDATED WELL SERVICE TICKET 313391 60/40 4% GEL 125 SXS

Plugged through: TBG

District: 02

Signed Bill Johnson  
(TECHNICIAN)