

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-06551-00-01
Spot: SENENW Sec/Twnshp/Rge: 31-18S-10W
4293 feet from S Section Line, 3116 feet from E Section Line
Lease Name: REIF B Well #: 4
County: RICE Total Vertical Depth: 3297 feet

Operator License No.: 30525
Op Name: LANGSTON, D. S.
Address: 310 W CENTRAL STE 202
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3294		
SURF	8.625	314		

\$107.15

Well Type: EOR UIC Docket No: E09151.7 Date/Time to Plug: 12/14/2007 9:30 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKES TESTING Company: MIKE'S TESTING & SALVAGE Phone: (620) 562-8088

Proposed Plugging Method: CIBP @ 3200'. RUN TUBING TO 2650' AND PUMP 35 SX'S CEMENT WITH CALCIUM CHROLIDE. PULL TUBING OUT OF HOLE AND PERFORATE @ 1250', 900'. AND 360'. RUN TUBING BACK DOWN TO 1250' AND PUMP 35 SX'S CEMENT. PULL TUBING TO 900' AND PUMP 35 SX'S CEMENT. PULL TUBING TO 360' AND CIRCULATE CEMENT TO SURFACE. PULL TUBING OUT HOLE AND TOP OFF.

Plugging Proposal Received By: JEFF KLOCK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/14/2007 2:00 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

CIBP @ 3200'. RUN TUBING TO 2650' AND PUMP 35 SX'S CEMENT WITH CALCIUM CHROLIDE. PULL TUBING OUT OF HOLE AND PERFORATE @ 1250', 900', AND 360'. RUN TUBING BACK DOWN TO 1250' AND PUMP 35 SX'S CEMENT. PULL TUBING TO 900' AND PUMP 35 SX'S CEMENT. PULL TUBING TO 360' AND CIRCULATE CEMENT TO SURFACE. PULL TUBING OUT OF HOLE AND TOP OFF.

Perfs:

INVOICED
DATE 1-4-08
INV. NO. 2008061017

RECEIVED
KANSAS CORPORATION COMMISSION
JAN 02 2008
CONSERVATION DIVISION
WICHITA, KS

Remarks: 60-40 POZ. 4% GEL. COPELAND TICKET C-33404

Plugged through: TBG

District: 02

Signed

Virgil Clothier

(TECHNICIAN)

PKT