


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

WELL PLUGGING RECORD



Rooks County. Sec. 4 Twp. 9 Rge. (E) 19 (W)  
Location as "NE/CNW/SW" or footage from lines CEL NW SE  
Lease Owner Natural Gas & Oil Corporation  
Lease Name McClellan B Well No. 2  
Office Address 1009 Central Building, Wichita 2, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) oil  
Date well completed March 10, 1949 19  
Application for plugging filed September 3, 1953 19  
Application for plugging approved September 4, 1953 19  
Plugging commenced December 30, 1953 19  
Plugging completed January 6, 1954 19  
Reason for abandonment of well or producing formation oil depleted to noncommercial production and water  
If a producing well is abandoned, date of last production August 24 1953  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well \_\_\_\_\_ Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface		0	242	8 5/8"	242	none
Arbuckle	oil	0	3440	5 1/5"	3440	510

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Total Depth 3443. Plugged with 5 sacks cement, 20' rock and 5 sacks cement. Shot casing off at 510 feet, pulled casing out of hole, pumped in 25 sacks mud and squeezed surface casing with 70 sacks cement to shut off Dakota water.

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Forbes Casing Pulling Company  
Address P O Box 221 Great Bend, Kansas


STATE OF Kansas, COUNTY OF Sedgwick, ss.  
Harold A. Burt, Regional Manager (employee of owner) or owner or operator of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Harold A. Burt  
1009 Central Building, Wichita, Kans  
(Address)

SUBSCRIBED AND SWORN TO before me this 21st day of January 19 54

Cather Linsell

My commission expires May 25, 1957 Notary Public.



1122/54

COMPANY: Westgate Greenland Oil Company  
 CONTRACTOR: Jackson Drilling Corporation  
 FARM: McClellan B-2  
 LOCATION: CEL NW/SE Section 4-9-19W  
 Rooks County, Kansas  
 ELEVATION: 2013  
 COMMENCED: February 18, 1949  
 COMPLETED: March 2, 1949 - Rotary  
 March 10, 1949 - Cardwell

0 to 40  
 40 to 217  
 217 to 390  
 390 to 490  
 490 to 610  
 610 to 940  
 940 to 1150  
 1150 to 1165  
 1165 to 1362  
 1362 to 1420  
 1420 to 1575  
 1575 to 1710  
 1710 to 1845  
 1845 to 2145  
 2145 to 2390  
 2390 to 2465  
 2465 to 2590  
 2590 to 2600  
 2600 to 2825  
 2825 to 2910  
 2910 to 3235  
 3235 to 3444  
 3444 T.D.

Soap Stone  
 Shale & shells  
 Shale  
 Shale & shells  
 Sand  
 Shale & shells  
 Sand  
 Shale  
 Shale & red bed  
 Red bed  
 Anhydrite  
 Shale & shells  
 Shale & lime Shells  
 Shale & shells  
 Lime  
 Shale & shells  
 Lime & shale  
 Shale  
 Lime & shale  
 Shale & shells  
 Lime & shale  
 Lime

*2012  
 1944  
 256 To Report*

8 5/8" casing set at 242 feet - Cemented with 135 sacks cement  
 5 1/2" casing set at 3440 feet - Cemented with 65 sacks cement

Top Arbuckle: 3440

Acidized - 500 gallons Dowell X service

Potential - ~~Minimum~~ - 25 Barrels - *Temperature* 271 Barrels

Measurements taken from top of derrick floor

C E R T I F I C A T E

I, Clare A. Stewart, do hereby certify that the above and foregoing is a true and correct copy of log of the McClellan B-2, Section 4-9-19W, Rooks County, Kansas, as reflected by files of the Jackson Drilling Corporation.

**PLUGGING**  
 FILE SEC 4 T 9 R 19W  
 BOOK PAGE 126 LINE 36

RECEIVED  
 STATE CORPORATION  
 SEP - 4 1949  
 CONSERVATION DIVISION  
 Topeka, Kansas

*Clare A. Stewart*  
 Clare A. Stewart

Subscribed and sworn to before me, a Notary Public, within and for Johnson County, Kansas, this 6th day of April, 1949

*Dorothy J. Wilson*  
 Dorothy J. Wilson