

15-163-21234-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER February 18, 1981

LEASE NAME Mc Clellan

WELL NUMBER #1

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

450 Ft. from S Section Line

990 Ft. from W Section Line

SEC. 4 TWP. 9s RGE. 19w (E) of (W)

COUNTY Rooks

Date Well Completed 2-18-81

Plugging Commenced 3-30-89

Plugging Completed 3-30-89

LEASE OPERATOR Christa Oil Co.

ADDRESS 25th & Vine - Dean Ellner Bldg. - Hays, Kansas

PHONE#(913) 628-1909 OPERATORS LICENSE NO. 03255

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on February 7, 1989 (date)

by Shari Feist (Director) (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? \_\_\_\_\_

Producing Formation Arbuckel Depth to Top 3477 Bottom 3481 T.D. 3481

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content     | From | To | Size  | Put In | Pulled out |
|-----------|-------------|------|----|-------|--------|------------|
| Arbuckel  | water & Oil |      |    | 8-5/8 | 256    |            |
|           |             |      |    | 5 1/2 | 3480   |            |

RECEIVED  
STATE CORPORATION COMMISSION

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from    feet to    feet for each set.

\* See Back Side -

APR 3 1989  
4/3/89  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this form.)


Name of Plugging Contractor Halliburton Services License No. 5287

Address 1100 E. 8th st. - Hays, Kansas 67601

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Christa Oil Co.

STATE OF Kansas COUNTY OF Ellis, ss.

Ted Luebbers (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.



(Signature) Ted Luebbers

(Address) 25th & Vine - Hays, Kansas 67601

SUBSCRIBED AND SWORN TO before me this 31 day of March, 1989

Brenda Hernandez  
Notary Public

My Commission Expires: 11-9-92

# CHRISTA OIL COMPANY

Oil Production

a subsidiary of PIONEER WESTERN CORPORATION

P. O. BOX 637 - OUTER WEST MAIN STREET  
ROBINSON, ILLINOIS 62454  
TELEPHONE 618-546-5602  
TELEFAX 618-546-1299

McClellan # 1

Location: Center of NW SE  
Section 4-9 S-19W  
Rooks, Kansas

Drilling Completed: February 18, 1981

DTD: 3485'  
LTD: 3481'

Casing/Cement Records:

8 5/8" - 256' - cemented with 95 sacks  
5 1/2" - 3480' - cemented with 150 sacks  
Bridge plug set at - 3444'

Formation Tops: Radiation Guard Log

Anhydrite - 1420'  
Heebner - 3148'  
Arbuckle - 3427'

Proposed Plugging Procedure:

1. Perforate Anhydrite at 1435' with three holes phased at 120°.
2. Perforate base of Dakota at approximately 758' with three holes phased at 120°.
3. Hook onto 5 1/2" casing and cement with 250 sacks 65-35 (Light Cement) with 10% gel, 2% Diacel, 1/4# per sack flocele, and 5 sacks of hulls.
4. Tie onto 8 5/8" and 5 1/2" annulus and cement to surface.

RECEIVED  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION  
Wichita, Kansas