

15-163-21405-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER Sept. 17, 1981

LEASE NAME McClellan

WELL NUMBER #2 SWD

990 Ft. from S Section Line

990 Ft. from E Section Line

SEC. 4 TWP. 9S RGE. 9W (E) or (W)

COUNTY Rooks

Date Well Completed Sept. 17, 1981

Plugging Commenced 3-30-89

Plugging Completed 3-30-89

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Christa Oil Co.

ADDRESS 25th & Vine - Dean Ellner Bldg. - Hays, Kansas

PHONE#(913) 628-1909 OPERATORS LICENSE NO. 03255

Character of Well SWD

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on February 7, 1989 (date)

by Shari Feist (Director) (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation Arbuckel & Granite Depth to Top 3514 Bottom 3619 T.D. 3619

Wash
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Arbuckel & G.W.	Water			8-5/8	249	
				5 1/2	3514	

Describe in detail the manner in which the well was plugged, indicating where the plug was placed and the method or methods used in introducing it into the hole. If cement were used, state the character of same and depth placed, from feet to feet each set.

* See back side -

RECEIVED
STATE CORPORATION COMMISSION
4/13/89
APR 13 1989

(If additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor Halliburton Services License No. 5287

Address 1100 E. 8th. St. - Hays, Kansas 67601


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Christa Oil Co.

STATE OF Kansas COUNTY OF Ellis, ss.

Ted Luebbers (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Ted Luebbers

(Address) 25 & Vine - Hays, Kansas 67601




Subscribed and sworn to before me this 31 day of March, 19 89

Brenda Memree
Notary Public

My Commission Expires: 11-9-92

Mc Clellan #2 SWD

RJ Halliburton, pump 50 sks class A and 275 sks 65-35
Poz Mix $\frac{1}{4}$ # flowseal per sk 8% gel 300# Huls down 5 $\frac{1}{2}$ " casing
Max press 400# SI 250#. Hook onto 5 $\frac{1}{2}$ 8-5/8 annulas and
pump 5 sks 65-35 Poz mix $\frac{1}{4}$ # flowseal per sk. 8% gel. Pressured
to 500# ok. Well plugged 11:40 A.M. - 3-30-89 - KCC Rep.
Marion Schmidt on location.



15-163-21405-00-00

CHRISTA OIL COMPANY

Oil Production

a subsidiary of PIONEER WESTERN CORPORATION

P. O. BOX 637 - OUTER WEST MAIN STREET
ROBINSON, ILLINOIS 62454
TELEPHONE 618-546-5602
TELEFAX 618-546-1299

McCLELLAN #2 SWD

Location: NW SE SE
Section 4-9 S-19W
Rooks, Kansas

Drilling Completed: September 17, 1981

DTD: 3619'

Casing/Cement Record:

8 5/8" - 249' - cemented with 140 sacks
5 1/2" - 3514' - cemented with 100 sacks
DV Tool- 1382' - cemented with 350 sacks with 6% gel

Disposal Zone:

Open hole - 3514'-3612'

Note: On January 3, 1989, Christa Oil Company was unable to reach TD of 3612' due to deposits of iron sulfide, barium sulfate and cement. Christa was able to clean the well bore out to 3554'.

Formation Tops:

Anhydrite - 1444'
Arbuckle - 3465'
Granite Wash - 3612'

RECEIVED
PIONEER WESTERN CORPORATION COMMISSION

CONSERVATION DIVISION
WICHITA, KANSAS