

API NUMBER 15-163-23,228-00-00

LEASE NAME Cerrow "A"

WELL NUMBER 8-4

4290 Ft. from S Section Line

3300 Ft. from E Section Line

SEC. 4 TWP. 9 SRGE. 19 (E) or (W)

COUNTY Rooks

Date Well Completed 9-7-93

Plugging Commenced 10-16-96

Plugging Completed 10-16-96

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR AFG Energy Inc.

ADDRESS P.O. Box 458 Hays, Ks. 67601-0458

PHONE# (913) 625-6374 OPERATORS LICENSE NO. 03456

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 10-14-96 (date)

by Marion Schmidt (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, Is well log attached? \_\_\_\_\_

Producing Formation Arbuckle - L-KC Depth to Top 3128' Bottom 3444' T.O. 3448'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Arbuckle	Oil & Water	<u>3441'</u>	<u>3444'</u>	<u>8 5/8"</u>	<u>320</u>	<u>None</u>
L-KC	Oil & water	<u>3128'</u>	<u>3242'</u>	<u>5 1/2"</u>	<u>3470</u>	<u>None</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set  
Hooked to 8 5/8" - Pressured up to 500#. Hooked to 5 1/2" & mixed 15 sxs. 60/40 Poz., 8% gel.  
Followed with 500# Hulls in 235 sxs. 60/40 Poz., 8% gel. Pressured to 1000#. SIP - 400#.  
Total sxs. 250.

Name of Plugging Contractor Allied Cementing License No. \_\_\_\_\_

Address Russell, Ks.


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: AFG Energy Inc.

STATE OF Kansas COUNTY OF Ellis, ss.

Terry W. Piesker (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Terry W. Piesker

(Address) P.O. Box 458 Hays, Ks. 67601-0458



AND SWORN TO before me this 29th day of October, 19 96

Linda K. Pfannenstiel  
Notary Public

My Commission Expires: 2/5/2000

USE ONLY ONE SIDE OF EACH FORM

