


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Graham County, Sec. 34 Twp. 9S Rge. 21 (E) 21 (W)
Location as "NE/CNW/SW" or footage from lines SW NW SE
Lease Owner Phillips Chemical Company
Lease Name Chem Desair Well No. 1
Office Address Bartlesville, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed January 25, 19 52
Application for plugging filed August 13, 19 57
Application for plugging approved August 16, 19 57
Plugging commenced August 21, 19 57
Plugging completed August 21, 19 57
Reason for abandonment of well or producing formation Uneconomical to operate

If a producing well is abandoned, date of last production May 24, 19 57
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Eldon Petty
Producing formation Arbuckle Depth to top 3875 Bottom _____ Total Depth of Well 3879 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Howard	Dry	3291		8 5/8"	345.88	None
Topeka	Dry	3320		5 1/2"	3875	None
Heebner	Dry	3503				
Toronto	Dry	3524				
IKC	Dry	3542				
Arbuckle	Oil	3875				

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Set Lane Wells Bridge plug at 3450'. Dumped 2 sx. Calseal on plug to 3430'. Pumped in 35 sx. Magogel mud from 3430' to 600' and 75 sx. cement in filling to base of cellar. Well Plugged and Abandoned at 11:00 AM 8/21/57

Note: 5 1/2" casing cemented to surface when well completed.

RECEIVED
STATE CORPORATION COMMISSION
AUG 24 1957
8-24-57
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Halliburton Oil Well Cementing Company
Address Duncan, Oklahoma.

STATE OF KANSAS, COUNTY OF BARTON, ss.
A. J. Willis

(employee of owner) or (~~owner~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
Box 779 - Great Bend, Kansas.
(Address)

SUBSCRIBED AND SWORN TO before me this 23rd day of August, 19 57

My commission expires November 18, 1957

[Signature]
Notary Public.

PLUGGING
FILE SEC 34 T. 9 S. R. 21 W.
BOOK PAGE 37 LINE 6

EXPLORATION RECORD

Lease Chem Desair

Well 1

Formation Name	Top	Base	Remarks
Sand - Shale	0	345	
Sand - Shale - Redbed	345	810	
Sand - Shale	810	1223	
Sand - Shale - Redbed	1223	1640	
Redbed- Pyrite - Anhydrite	1640	1910	
Lime and Shale	1910	2178	
Shale - Chalk - Lime Strks	2178	2366	
Lime and Shale	2366	2904	
Shale - Chalk - Lime	2904	3015	
Lime and Shale	3015	3879	

RECEIVED
STATE CORPORATION COMMISSION
AUG 24 1957
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 34 T 9 R 21W
BOOK PAGE 37 LINE 6