


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission

P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Graham County. Sec. 34 Twp. 9S Rge. (E) 21 (W)
Location as "NE/CNW/SE" or footage from lines. SW SW SE
Lease Owner A. L. Abercrombie, Inc.
Lease Name DESAIR Well No. 3
Office Address 801 Union Center, Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed Unknown - Purchased from Phillips Pet. Co. 19 73
Application for plugging filed April 17, 19 73
Application for plugging approved April 18, 19 73
Plugging commenced June 28, 19 73
Plugging completed June 28, 19 73
Reason for abandonment of well or producing formation Non-Commercial

If a producing well is abandoned, date of last production March 30, 19 73
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Bill Nichols
Producing formation Arbuckle Depth to top 3661 Bottom 3671 Total Depth of Well 3865 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5 1/2"	3888'	0
				8-5/8"	298'	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Pumped and squeezed perforations with 1 sack hulls, 20 sx. cement and 28 sx. gel. Max. pump PSI 1500#. Bled off PSI and pumped 10 sx. cement. Shut in PSI 1000#.

RECEIVED
STATE CORPORATION COMMISSION
OCT 15 1973
10-15-73
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Abercrombie Drilling, Inc.
Address 801 Union Center, Wichita, Kansas 67202

STATE OF KANSAS COUNTY OF SEDGWICK ss.
Jerry A. Langrehr (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jerry A. Langrehr
801 Union Center, Wichita, Kansas 67202 (Address)

SUBSCRIBED AND SWORN TO before me this 8th day of October, 19 73

My commission expires February 10, 1975
Beverly Mann Notary Public.

Formation Record

Lease

Desair

Well No. 3

FROM	TO	Formation	REMARKS
0	148	Surface Sand and Clay	
148	1603	Sand and Shale	
1603	2100	Red bed, Pyrite and Anhydrite	
2100	2302	Red bed, Shale and Lime Streaks	
2302	2525	Lime and Shale	
2525	2686	Shale, Chalk, and Lime Streaks	
2686	2856	Lime and Shale	
2856	2981	Shale, Chalk and Lime	
2981	3802	Lime and Shale	
			Tops:
			Howard 3299
			Topeka 3330
			Heebner 3510
			Toronto 3527
			L. K. C. 3549
			Base L. K. C. 3774
3802	3851	Lime, Shale, Chert and Chalk	
3851	3871	Lime and Shale	Top Arbuckle 3861

RECEIVED
STATE CORPORATION COMMISSION
APR 18 1973
CONSERVATION DIVISION
Wichita, Kansas