

15-065-01123-00-00


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027

WELL PLUGGING RECORD

Wichita, Kansas 67217
NORTH



Locate well correctly on above
Section Plat

Graham County. Sec. 34 Twp. 9S Rge. (E) 21 (W)
Location as "NE/CNWK/SW" or footage from lines C E/2 SW SE
Lease Owner A. L. Abercrombie, Inc.
Lease Name DESAIR Well No. 4
Office Address 801 Union Center, Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed Unknown - Purchased from Phillips Pet. Co. 19
Application for plugging filed April 17, 19 73
Application for plugging approved April 18, 19 73
Plugging commenced June 28, 19 73
Plugging completed June 28, 19 73
Reason for abandonment of well or producing formation Non-Commercial

If a producing well is abandoned, date of last production March, 19 71
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Bill Nichols
Producing formation Arbuckle Depth to top 3858 Bottom 3865 Total Depth of Well 3865 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	325'	0
				5-1/2"	3887'	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Perforations squeezed and casing filled with cement to 3750'
filled with gel 3750' to 950'
filled with cement 950' to 50'
filled with cement 50' to surface
Max. pump PSI 1150#
Shut in PSI 1000#

RECEIVED
STATE CORPORATION COMMISSION
OCT 15 1973
10-15-73
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Abercrombie Drilling, Inc.
Address 801 Union Center, Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Jerry A. Langrehr (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jerry A. Langrehr
801 Union Center, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 8th day of October, 19 73

My commission expires February 10, 1975
Beverly Mann Notary Public.

Formation Record

Lease

Desair

Well No.

4

FROM	TO	Formation	REMARKS
0	345	Shale and Sand.	
345	890	Sand-Shale-Redbed.	
890	1253	Shale and Sand.	
1253	1655	Shale-Sand-Redbed.	
1655	1915	Redbed-Pyrite-Anhydrite.	Top Anhydrite - 1765' Base - 1810'
1915	2178	Lime and Shale.	
2178	2376	Shale-Chalk-Lime Streaks.	
2376	2906	Lime and Shale.	
2906	3017	Shale-Chalk-Lime.	
3017	3865	Lime and Shale.	

Tops:

Howard - 3290
 Topeka - 3382
 Heebner - 3502
 Toronto - 3524
 LKC - 3542
 Base LKC - 3768
 Arbuckle - 3857

RECEIVED
 STATE CORPORATION COMMISSION
 APR 18 1973
 CONSERVATION DIVISION
 Wichita, Kansas