

RECEIVED

WELL PLUGGING APPLICATION

NOV 21 2007

This Form must be Typed Form must be Signed All blanks must be Filled

Please TYPE Form and File ONE Copy

15-035-19282-0000

CONSERVATION DIVISION WICHITA, KS

API # 15 - none (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

indicate original spud or completion date spud 5/27/1951

Well Operator: Ron Whiteman dba/Gen-Dor Oil Company KCC License #: 9576

Address: 8135 281st rd City: Cambridge

State: Kansas Zip Code: 67023 Contact Phone: (620) 467 - 2615

Lease: Stolp Well #: 5 Sec. 29 Twp. 30 S. R. 7 [x] East [] West

SE NE NE Spot Location / QQQQ County: Cowley

990 Feet (in exact footage) From [x] North / [] South (from nearest outside section corner) Line of Section (Not Lease Line)

330 Feet (in exact footage) From [x] East / [] West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: [x] Oil Well [] Gas Well [] D&A [] Cathodic [] Water Supply Well [] SWD Docket # [] ENHR Docket # [] Other:

Conductor Casing Size: Set at: Cemented with: Sacks

Surface Casing Size: 8 5/8 Set at: 47 Cemented with: 45 Sacks

Production Casing Size: 5 1/2 Set at: 2868 Cemented with: 35 Sacks

List (ALL) Perforations and Bridgeplug Sets: open hole from 2868 to 2894.5 (MISS), squeeze holes @2450 ft (cemented with 150 sx) perfs in the KC from 2255 to 2261 and 2314 to 2320

Elevation: 1470 ([] G.L. / [] K.B.) T.D.: 2894.5 PBTD: Anhydrite Depth: unknown (Stone Corral Formation)

Condition of Well: [] Good [] Poor [x] Casing Leak [] Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): fill bottom of hole with sand to 50 ft above perfs and dump-bail 6sx cement on top, for top plug circulate cement from 350 ft to surface

(the Miss has a 50' sand plug with 6 sx cement on top of it and there is a cement plug from 2385' to 2450')

Is Well Log attached to this application as required? [x] Yes [] No Is ACO-1 filed? [] Yes [x] No

If not explain why? upon completion of the lower KC we did not see any oil just a little water so we deemed the well to be plugged

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Ronnie Whiteman (cell # 620-222-4316)

Phone: (620) 467 - 2615

Address: 8135 281st rd City / State: Cambridge, Kansas 67023

Plugging Contractor: Gen-Dor Oil Company KCC License #: 9576

Address: 8135 281st rd Phone: (620) 467 - 2615

Proposed Date and Hour of Plugging (if known?): will call in to district office

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 3/17/2007 Authorized Operator / Agent: Bert Whiteman (Signature)



CORPORATION COMMISSION

Kathleen Sebelius, Governor Thomas E. Wright, Chairman Michael C. Moffet, Commissioner Joseph F. Harkins, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

WHITEMAN, RON DBA GEN-DOR OIL CO.
8135 281ST RD
CAMBRIDGE, KS 67023-9308

January 08, 2008

Re: STOLP #5
API 15-035-19282-00-00
29-30S-7E, 990 FNL 330 FEL
COWLEY COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division has received your plugging proposal, form CP-1, for the above well and has reviewed the proposal for completeness. The central office will now forward your CP-1 to the district office listed below for review of the proposed plugging method. **Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit in accordance with K.A.R. 82-3-600.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. This notice in no way constitutes authorization to plug the above well by persons not having legal rights of ownership or interest in the well.

This notice is void after July 6, 2008. The CP-1 filing does not bring the above well into compliance with K.A.R. 82-3-111 with regard to the Commission's temporary abandonment requirements.

Sincerely,

Steve Bond
Production Department Supervisor

District: #2
3450 N. Rock Road, Suite 601
Wichita, KS 67226
(316) 630-4000