

9

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH

			X

Locate well correctly on above
Section Plat

Morris County. Sec. 26 Twp. 16 Rge. 5 (E) (W)
Location as "NE/CNW/SW" or footage from lines NE NE SE
Lease Owner R.W. Wiggins
Lease Name Peterson Well No. 3
Office Address Delavan, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil Well
Date well completed 3-24-51 19
Application for plugging filed 7-18-67 19
Application for plugging approved 7-19-67 19
Plugging commenced 7-27-67 19
Plugging completed 7-29-67 19
Reason for abandonment of well or producing formation depleted

If a producing well is abandoned, date of last production _____ 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Hugh Scott
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 2267 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	164	none
				4 1/2	2229	1911'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Fill hole with sand from 2267' to 2225' and dump 4 sacks of cement

Mud hole to 160'

Set 10' rock bridge from 160' to 150' and dump 25 sacks of cement

Mud hole to 40', rock bridge from 40' to 30' and dump 10 sacks of cement

RECEIVED
AUG 3 1967

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Flint Engineering and Const. Co.
Address 2375 W. Central El Dorado, Kansas

STATE OF Kansas, COUNTY OF Butler, ss.

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jessie Davis

SUBSCRIBED AND SWORN TO before me this 2 day of August, 19 67

My commission expires Sept. 27, 1967
Ronald P. Hansen Notary Public.

15-127-19009-00-00
 KANSAS GEOLOGICAL SOCIETY
 KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
 KANSAS GEOLOGICAL SOCIETY BUILDING
 508 EAST MURDOCK WICHITA, KANSAS

COMPANY KOESTER & Mergen

26 16 5E
 NE NE SE

FARM Petersen 3

MEXXN Morris

TOTAL DEPTH 2267'

LOG NO. 3-8-51

DATE 3-24-51


SHOT OR BREAK

LOGGING Slusser Drlg. Co.

DATE 9-8-51

CASIN

20	10	
15	8	164'
12	6	
13	K 4	2229'



25 BO, some wtr.

surface soil	10
yellow clay, lime	85
brkn lime	164
lime, shale	240
shale, lime	310
lime, shale	400
shale, lime	480
shale, shells	1075
shale, lime	1385
lime	1415
lime, shale	1475
lime	1535
shale	1585
shale, lime	1680
lime, shale	1750
lime	1780
lime	1985
shale, shells	2130
lime, shale	2195
shale, lime	2226
chat	2267
Total Depth	

FIGURES INDICATE BOTTOM OF FORMATIONS

TOPS:
 Chat 2226

DST: 9 stands oil 5 stands oil & mud, shut in pressure 680#. 30 min.
 Fillup: 1300' of fluid overnight.

RECEIVED
 STATE CORPORATION COMMISSION

JUL 19 1967

CONSERVATION DIVISION
 Wichita, Kansas

2267
2226
41

2229
2226
3

67
26
41

Kenneth
 this Log doesnt say how much
 cement was put in but Mergen and
 never used more than 35 sacks all the
 well was 25 sacks.
 See you *Puller*