


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Morris County, Sec. 26 Twp. 16 Rge. 5E (E) 11(W)

Location as "NE/CNW/SW" or footage from lines SE SE NE
Lease Owner R. W. Wiggins
Lease Name M. R. Peterson Well No. 1 SWD
Office Address Box 295 Delavan, Kansas 66347
Character of Well (completed as Oil, Gas or Dry Hole) SWD
Date well completed 19
Application for plugging filed 2/19/68 19
Application for plugging approved 2/19/68 19
Plugging commenced 3/20/68 19
Plugging completed 3/20/68 19
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Hugh Scott
Producing formation Depth to top Bottom Total Depth of Well 2881' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

8 5/8" - 169' - Circulated w/cement. 4 1/2" 2880' - Circulated w/cement.
Sand hole from 2881' to 2500'. Cement 2500' to 2450'. Mud 2450' to 180'. Bridge 180' to 170'. Cement 170' to 100'. Mud 100' to 50'. Bridge 50' to 40'. Cement 40' to 0. No Pipe Pulled.

RECEIVED
STATE CORPORATION COMMISSION
3/26/68
MAR 26 1968
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor R. W. Wiggins
Address Delavan, Kansas 66347

STATE OF Kansas, COUNTY OF Richardson, ss.
R. W. Wiggins (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. W. Wiggins
Delavan, Kansas 66347
(Address)

SUBSCRIBED AND SWORN TO before me this 25 day of March, 1968

My commission expires Feb 18 1970 Notary Public.

15-127-19001-00-00
 WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
 508 East Murdock, Wichita, Kansas


R

Company- R. L. MENDENHALL
 Farm- Peterson No. 1

SEC. 26 T. 16 R. 5E
 SE SE NE

Total Depth. 2281
 Comm. 9-1-51 Comp. 9-11-51
 Shot or Treated.
 Contractor. Mendenhall Drlg. Co.
 Issued. 10-13-51

County Morris
 KANSAS



CASING:

8 5/8" 169'

Elevation. _____

Production. Dry

Figures Indicate Bottom of Formations.

shale & shells	30
lime broken	71
shale & lime	134
lime	156
shale & lime	460
R. R.	470
shale	485
shale & lime	1735
lime	1770
lime & shale	1800
lime	1960
shale	1970
lime	2010
shale & shells	2205
chat	2266
lime	2281
Total Depth	

Scout Tops:

Miss.	2206
Kinderhook Shale	2272

Deepening
 3-30-56 4-6-56

Cement	0-20
Thru hole	20-150
Cement	150-180
Wash down	180-2280
lime	2280-2305
Shale	2305-2495
lime arbuckle	2495-2880
Total Depth	2880
Set 4 1/2" @	2880

REGISTRATION COMMISSION
 JAN 5 1957
 CONSERVATION DIVISION
 WICHITA, KANSAS