

STATE OF KANSAS  
STATE CORPORATION COMMISSION


Form CP-4

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

GRAHAM County. Sec. 13 Twp. 9 Rge. 22 (EX) (W)  
Location as "NE/CNW/SW" or footage from lines SW NW SE  
Lease Owner UNION TEXAS PETROLEUM  
Lease Name BUSS "D" Well No. 2  
Office Address 1740 BROADWAY, SUITE B 400, DENVER, COLORADO  
Character of Well (completed as Oil, Gas or Dry Hole) oil  
Date well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging approved \_\_\_\_\_ FEBRUARY 20 19 67  
Plugging commenced \_\_\_\_\_ APRIL 15 19 67  
Plugging completed \_\_\_\_\_ APRIL 24 19 67  
Reason for abandonment of well or producing formation DEPLETED

NORTH



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well W. L. NICHOLS  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3802' Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	248'	none
				5-1/2"	3801'	1110.18'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

3802' - 3790' - sand  
3790' - 3750' - 5 sacks cement  
3750' - 225' - pumped 47 sacks jel mud & 6 sacks hulls  
225' - base - pumped 75 sacks cement

RECEIVED  
5/11/67  
MAY 1 1967  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor SANTA-FE PIPE & SUPPLY, INC.,  
Address BOX 562, GREAT BEND, KANSAS

STATE OF KANSAS COUNTY OF BARTON, ss.  
T. L. NUTT

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) T. L. Nutt

BOX 562, GREAT BEND, KANSAS  
(Address)

SUBSCRIBED AND SWORN to before me this 29 day of APRIL, 1967

My commission expires JULY 31, 1970

Mary M. Guenier  
Notary Public.

RECEIVED  
FEB 20 1957  
DIVISION

DRILLER'S LOG

Company: Anderson-Prichard Oil Corp.

SW NE SE  
Sec. 13, Twp. 9S, Rge. 22W,

Farm: Base "D" Well No. 2  
Comm: 8-15-51 Comp: 8-24-51

County: Graham,  
Kansas

Total Depth: 3801'  
Contractor: Glenn W. Peol

Elevation:

Casing:  
8 5/8" 248' con.  
5 1/2" 3800' con.

Production:

Figures below indicate bottom of formations

Clay & Sand	0 -	250
Shale		350
Shale & Shells		615
Sand		935
Shale & Shells		1250
Sand & Shale		1400
Shale		1790
Anhydrite		1825
Shale		2040
Shale & Shells		2280
Shale & Lime		2645
Broken Lime		2815
Lime & Shale		3200
Lime		3435
Lime & Shale		3465
Lime		3801
Total Depth		3801

This is to certify that the above information is, to the best of our knowledge true and correct.

GLENN W. PEOL

BY: Wm Herbert

SUBSCRIBED AND SWORN to before me this 29<sup>th</sup> day of August, 1951.

My commission expires June 4, 1955 Marian M. Herbert  
Notary Public