

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-065-02260-00-01

API NUMBER Comp. 10-9-51

LEASE NAME Buss "C"

WELL NUMBER 4

SPOT LOCATION SE SW NE

SEC. 13 TWP. 9 RGE. 22 (X) or (W)

COUNTY Graham

Date Well Completed 10-9-51

Plugging Commenced 11-5-85

Plugging Completed 11-5-85

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Samson Resources Company

ADDRESS Two West Second Street, Tulsa, Okla. 74103

PHONE # (918) 583-1791 OPERATORS LICENSE NO. 5463

Character of Well SWD
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? District #6 - Hays, Kansas

Is ACO-1 filed? No If not, is well log attached? Yes

Producing formation Arbuckle Depth to top 3803 bottom 4233 T.D. 4289

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Arbuckle	Water	Surf.	254	8-5/8"	252	None
		Surf.	3804	5-1/2"	3804	None
		3752	3878	4-1/2"	106	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Halliburton mixed and pumped 300 sacks of 60-40 POZ mix with 10% gel, 1/4 lb of Flocele per sack and 5 sacks of Hulls down 5-1/2" casing at 1200 psi max and closed in with 600 psi. Mixed and pumped 150 sacks of POZ mix with 10% gel, 1/4 lb. of Flocele per sack and 2 sacks of Hulls down 8-5/8" casing at 500 psi max and closed in at 0 psi.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Samson Resources Company License No. 5463

Address Two West Second Street

Tulsa, Oklahoma 74103

STATE OF Oklahoma COUNTY OF Tulsa, ss.

R. J. Davis

(employee of operator) or

(operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. J. Davis

Two West Second Street

(Address) Tulsa, Oklahoma 74103

SUBSCRIBED AND SWORN TO before me this 6 day of December, 1985

My Commission expires: July 24, 1986

RECEIVED
John E. Schroeder
STATE CORPORATION COMMISSION Notary Public

12/9/85
DEC 9 1985

CONSERVATION DIVISION
Wichita, Kansas

Form CP-4
Revised 01-84

DRILLER'S LOG

Company: Anderson-Prichard Oil Corp.

Farm: Buss "C" Well No. 4

Total Depth: 3807

Comm: 9-28-51 Comp: 10-9-51

Contractor: Glenn W. Peel

Casing:

8 5/8" 252' cem.
5 1/2 3804' cem.

~~SE~~ 1/4 SW/4 NE/4
Sec. 13, Twp. 9S, Rge. 22W

County: Graham, Kansas

Elevation:

Production:

Figures below indicate bottom of formations

Surface Clay	0 -	252
Shale		900
Sand & Shale		1225
Shale		1310
Shale & Shells		1665
Anhydrite		1700
Shale		1990
Shale & Lime		2330
Lime		2545
Lime & Shale		3350
Lime		3695
Lime & Shale		3755
Lime		3790
Lime & Shale		3804
Lime		3807
Total Depth		3807

This is to certify that the above information is, to the best of our knowledge true and correct.

GLENN W. PEEL

BY: Wm Herbert

SUBSCRIBED AND SWORN to before me this 12th day of October, 1951.

My commission expires June 4, 1955 Marvin M. Herbert
Notary Public

RECEIVED
STATE CORPORATION COMMISSION
DEC 9 1955
CONSERVATION DIVISION
Wichita, Kansas