


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Graham County. Sec. 20 Twp. 9S Rge. (E) 22 (W)
Location as "NE/CNW/SW" or footage from lines C SW NW
Lease Owner Chief Drilling Co., Inc.
Lease Name Rice Estate Well No. 1
Office Address Box 797 - Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 3/19 19 64
Application for plugging filed 3/19 19 64
Application for plugging approved 3/19 19 64
Plugging commenced 3/19 19 64
Plugging completed 3/19 19 64
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W.L. Nichols - Moreland, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3890 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	181	8-5/8"	181	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Wooden plug set @ 540'
Mixed 20 sacks cement through drill pipe
Wooden plug set @ 180'
Mixed 20 sacks cement through drill pipe
1/3 sack hulls and wooden plug set @ 40'
Mixed 10 sacks cement through drill pipe

RECEIVED
STATE CORPORATION COMMISSION
3/26/64
MAR 26 1964
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Chief Drilling Co., Inc.
Address Box 797 - Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
V. Richard Hoover, President (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.
(Signature) Chief Drilling Co., Inc.
Box 797 - Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 20th day of March, 1964

My commission expires Jan. 26, 1967
Carmen R. Cook Notary Public.

WELL LOG

Chief Drilling Co., Inc.
Box 797
Great Bend, Kansas

RICE ESTATE #1
C SW NW Sec. 20-98-22N
Graham County, Kansas

Contractor: Chief Drilling Co., Inc.

Commenced: 3/12/64
Completed: 3/19/64

Casing Record: 8-5/8" @ 181' w/140 sacks OL-3 & 2 sacks Gal.

DRY & ABANDONED

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>ELEVATION</u>
Surface Sand & Gravel	0	40	2396 Cr.
Shale	40	181	2395 O.F.
Shale with Sand streaks	181	1500	2401 N.B.
Sand	1500	1680	
Shale & Shells	1680	1934	<u>FORMATION TOPS</u>
Anhydrite	1934	1972	Anhydrite 1934 - 487
Shale & Shells	1972	2150	Reebner 3626 - 1225
Shale & Lime	2150	2870	Toronto 3646 - 1245
Lime	2870	2890	Lansing 3660 - 1259
Lime & shale	2890	3085	Total Depth 3890 - 1489
Lime	3085	3626	
Lime & shale	3626	3660	
Lime	3660	3890	
Total Depth	3890		

STATE OF KANSAS, COUNTY OF BARTON) SS

I hereby certify that the above is a true and correct copy of the Driller's Log of the well drilled in the C SW NW Sec. 20-98-22N, Graham County, Kansas, to the best of my knowledge and belief.

CHIEF DRILLING CO., INC.
V. Richard Hoover
V. Richard Hoover, President

Subscribed and sworn to before me this 23rd day of March, 1964.

Carmen E. Cook
Carmen E. Cook, Notary Public

My commission expires: Jan. 26, 1967.

RECEIVED
STATE CORPORATION COMMISSION

MAR 24 1964

CONSERVATION DIVISION
Wichita, Kansas