

*R*

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
211 North Broadway  
Wichita, Kansas

FILE NO. 112-24

LOCATION SW SW SW

SEC. 24 TWP. 9 RGE. 22

Dry Hole  Abandoned Oil Well \_\_\_\_\_ Abandoned Gas Well \_\_\_\_\_

I have this date completed supervision of plugging of:

Well No. 1 Lease Kern

Operator Magnolia Pet Co Address Box 770 Great Bend, Kans

Field \_\_\_\_\_ County Graham

Total Depth 3985 Feet.

Plugging Contractor Ace Pipe Pulling

Plugging Contractor's License No. 2

Address \_\_\_\_\_

(Describe briefly the manner in which the well was plugged)

9 5/8" at 258' circulated with cement - 5 1/2" at 3570'

with 150 sax cement behind - Cement to 3928' - perforated at  
3572'.

Filled with sand to 3550', set 4 sax cement with dump bailer,  
pulled 2825' 5 1/2" - filled hole with mud to 250', set rock  
and 20 sax cement, mud to 50', set rock and 10 sax cement to  
bottom cellar.

RECEIVED  
STATE CORPORATION COMMISSION  
4/26/55  
APR 26 1955

*Edwin Letty*  
District Conservation Agent

CONSERVATION DIVISION  
Wichita, Kansas

DATE 4-23-55

PLUGGING  
FILE SEC 24 T 9 R 22W  
BOOK PAGE 112 LINE 24