

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
2/28/74
FEB 28 1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name C & G Drilling Company,

Complete Address 1107 Union National Building, Wichita, Kansas.

Lease Name Zvolanek Well No. 1

Location NW-NW-NW Sec. 24 Twp. 9 Rge. (E) (W) 22

County Graham Total Depth 3980'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Above

Address License No.

Operation Completed: Hour 4:00 PM Day 16 Month 2 Year 1974

The above well was plugged as follows:

200'--8 5/8" Surface casing, cement circulated with 150 Sx.
Top of Dakota section @ 575'.

Circulated hole with heavy mud. Pulled DP to 800' and displaced 110 Cu. Ft. cement
thru DP from 800' to 475'. Pulled DP to 215' and displaced 30 Cu. Ft. cement thru
DP from 215' to 140'. Pulled DP, set bridge @ 40' with 1/4 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: W. L. Dinkel
Well Plugging Supervisor

INVOICED

DATE 2/28/74

INV. NO. 8672-W