

KANSAS

FORM CP-3
Rev. 11-3-80

STATE CORPORATION COMMISSION

15-065-01537-00-00

CONSERVATION DIVISION AGENT REPORT

API Number 15- - (none) ✓

245 North Water
Wichita, KS 67202

Operator's Full Name Cities Service Co

Complete Address 700 Sutton Pl. Bldg. 209E. Williams Wichita Ks.

Lease Name Barber. "C" Well No. #1

Location NW-NE-SW- Sec. 26 Twp. 9 Rge. 22 (East) (West)

County Graham Total Depth 3825

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Cities Service Co.

Address 209E. Williams Wichita Ks. License No. _____

Operation Completed: Hour 3:45^{PM} Day 23 Month Jan Year 1981

The above well was plugged as follows:

9 P. 245' of 8 5/8" cwc 200 sx. 2 7/8" Tubing set @
3819 - Bottom Plug w/300 sx. DV. Tool @ 1860' cemented
w/500 sx Conn. & 250 sx Strata Streatorite To Surface.
Perf. 3650 to 3757. Pumped down. 2 7/8" Tubing.
175. sx. cem. 50' Per. Max Pres. 500 lbs. Shut in Pres 250 lbs.
Cemented By Halliburton.

1/26/81
JAN 26 1981

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Conservation Division Agent

INVOICED

DATE 2/18/81
INV. NO. 4507-W

WELDCAT

DISCOVERY

POOL

COMPANY Cities Service Oil Co. WELL # 1 FARM Barber "C"

LOCATION 330' South and 990' West of Center

Section 26, Township 9, Range 22 W.

2369 K.B., 2366 D.F.

ELEV. 2361 Gr., 2362 G.T.D.F. CO. ... STATE Kansas

IP. 37 oil, 1 1/2 water, 24 hours, May 72,

PERFS. ...

FRAC. ... ACID 4,000 gals.

T.D. 3820' PBTD 3808' GRAV/GOR ...

DRLG. COMM. 4-12-63 COMP. 4-23-63 CONTRACTOR Peel Bros., Inc.

CASING RECORD:

8-5/8" at 245' with 200 sacks cement.
 2-7/8" tubing at 3819' with 300 sacks cement
 DV tool at 1860' with 500 sacks cement
 and 250 cubic feet Stratocrete.

SLOPE TESTS (SYFO):

500' - 1 1/2"
 1000' - 1 1/2"
 1500' - 1 1/2"
 2000' - 1 1/2"
 2500' - 1 1/2"
 3000' - 1 1/2"
 3500' - 1 1/2"

FORMATION RECORD:

clay and sand	0-40
lime	48
sand and shale	115
shale	245
shale, shells and sand	1105
shale and shells	1300
sand and shale	1495
shale and shells	1837
anhydrite	1874
shale and shells	1990
shale and lime	2490
lime and shale	2597
lime	2780
lime and shale	2900
lime	3020
lime and shale	3415
lime	3820

3825 Rotary T.D.=3820 S.L.M. from
 cable tool floor 1' above ground level.

JAN 15 1961

GENERAL INVESTIGATION
 DIVISION